

| | MACHINE SPECIFICATIONS | 4 Lane |
|----|---|------------------|
| | As at 13 April 2011 | BEAST |
| | | MACHINE |
| 1 | Bag/Pouch Type | PILLOW |
| | Bag Size Range | 2LT - 220LT |
| 3 | Selection (suitable for max. output bags per month) | 4 000 000 |
| 4 | General Output: 2LT to 5LT bags per hour | 7200 |
| 5 | 10LT to 25LT bags per hour | 4500 |
| | 220LT bags per hour | 600 |
| 7 | Material Web Width (maximum) | 1500mm |
| 8 | Material Roll Diameter (maximum) | 800mm |
| | Index Accuracy/Draw Length Accuracy | +/- 2mm |
| | Side Track Accuracy/Web Guide Accuracy | +/- 2mm |
| | Compact Material Loading Gantry | No |
| | 4 Reel Driven Unwind System: Configuration | 2 sets x 2 reels |
| | Reel Core Shafts (76mm or 152mm) 2 are spare for pre-load | 6 Air |
| | Web Edge Guide System (side tracking of film) | Auto |
| | Static Induction (to cling webs\minimise air in between layers) | Yes |
| | Dancer Arm Accumulator System (tension control) | Yes |
| | Independent Servo Driven Draw (pull) Roller Stations | 3 |
| | Hole Punch & Cut Out / Waste Removal | Vacuum |
| | Web Splice Detection Unit | Yes |
| | Gland Feed Bowl | 2 |
| | Gland Bulk Storage Bin (for up to std 1" fitments) | 2 |
| | Automatic Tap, Cap Unit (cost includes std number of tap types) | 3 |
| | Tap Vibratory Bowl | 4 |
| | Tap Bulk Storage Bin | 2 |
| | Side Seal Station: Effective sealing length | 700mm |
| | Cross Seal Station: Effective sealing length | 1510mm |
| | Delta / Shaped Corner Seal Unit | Optional |
| 28 | Combination Rotary Perforator and/or Cut Off Unit | Servo |
| | Delivery Table(s) (with stacking assist*) | Yes |
| | Web Spreader Unit Sets Included | 5 |
| 31 | Coding / Dating / Marking Equipment Included | Not Available |
| | Modem Link (direct communication facility) | Yes |
| | CE Rating (safety rating) | Yes |
| 34 | Light Curtain (additional machine perimeter safety) Included | Optional |
| | Operator Manual, Program, Drawings, Instructions | Yes |
| 36 | Key Spares Included | Yes |
| | Warranty (months) from date of installation (parts & labour) | 18 |
| | Delivery from date of order (weeks) | 30 |
| 39 | Machine "footprint" area required length x width (approx) | 17m x 6,5m |
| | Machine Electrical Power Requirements (380V,3-Phase,50HZ) | 50 KVA |
| 41 | Air requirements (approx): - Output free air delivery | 5000 L /min |

| - Operating pressure | 6 BAR |
|----------------------|-------|
| - Motor power | 37 KW |